

**ADDENDUM NO. 3
TO
CONTRACT NO. 070F 02 C2
INTAKE NO. 3 - CONNECTOR TUNNEL**

SOUTHERN NEVADA WATER AUTHORITY

This Addendum No. 3 consists of 1 page of text. It is the responsibility of the Bidder to assure and guarantee by acknowledging the receipt of this Addendum in the Bid Form that the Bidder has received the Addendum in its entirety, and that the Bidder accepts all conditions contained herein. The required modifications are outlined below.

ADDENDUM NO. 1

1. Item 12, delete item in its entirety and replace with the following:

"GEOTECHNICAL BASELINE REPORT

Page 23 of 30, Item 7.2.1, under sub-heading Joints and Foliation, second paragraph, delete the last sentence and replace with the following sentence:

It is anticipated that final support of such wedges and blocks will require rock bolts, steel ribs and lagging, shotcrete, welded wire fabric, mine straps, or other support elements, or a combination thereof. Initial ground support such as rock bolts/dowels, shotcrete, welded wire fabric, mine straps, or other support elements, or a combination thereof, should also be anticipated."

2. Item 16, delete item in its entirety and replace with the following:


"GEOTECHNICAL BASELINE REPORT

Page 27 of 30, Item 8.2.1, under sub-heading Joints and Foliation, second paragraph, delete the last sentence and replace with the following sentence:

It is anticipated that final support of such wedges and blocks will require rock bolts, steel ribs and lagging, shotcrete, welded wire fabric, mine straps, or other support elements, or a combination thereof. Initial ground support such as rock bolts/dowels, shotcrete, welded wire fabric, mine straps, or other support elements, or a combination thereof, should also be anticipated."

END OF ADDENDUM

SOUTHERN NEVADA WATER AUTHORITY



Marcus R. Jensen, P.E.
Director of Engineering

1 MAY 2009
Date